

P08-0077, Rubber Chip Seal

I	Contractor application cost per square yard to include 1/4" or 3/8" Nominal Size Pre-Coated Hot Aggregate as designated. Rubberized Asphalt Cement Application (Rate will be 0.60 Gallon/Square Yard. Can be changed within a Range of 0.55 to 0.65 Gallon/Square Yard). Flush Coat (QS-1h) .08 Gallons per square Yard. Any material, equipment, labor or additional costs to be compliant with the contract.		Cactus Asphalt
			Unit Price
			Total
Ia.	1/4" Nominal Size Pre-Coated Hot Aggregate @ 25-35 lbs. per Sq. Yard		
	Less than 25,000 Square Yards – Cost per	1	SY \$3.47
	25,001 to 50,000 Square Yards – Cost per	1	SY \$3.20
	50,001 to 75,000 Square Yards – Cost per	1	SY \$3.14
	75,001 to 100,000 Square Yards – Cost per	1	SY \$3.16
	100,001 to 125,000 Square Yards – Cost per	1	SY \$3.16
	125,001 to 150,000 Square Yards – Cost per	1	SY \$3.16
	150,001 to 200,000 Square Yards – Cost per	1	SY \$3.16
	200,001 to 225,000 Square Yards – Cost per	1	SY \$3.16
	225,001 to 250,000 Square Yards – Cost per	1	SY \$3.16
	250,001 and Over – Cost per	1	SY \$3.16
Ib.	3/8" Pre-Coated Hot Aggregate @ 20-30 lbs. per Sq. Yard		
	For Low Volume Traffic Only		
	Less than 25,000 Square Yards – Cost per	1	SY \$3.50
	25,001 to 50,000 Square Yards – Cost per	1	SY \$3.20
	50,001 to 75,000 Square Yards – Cost per	1	SY \$3.17
	75,001 to 100,000 Square Yards – Cost per	1	SY \$3.17
	100,001 to 125,000 Square Yards – Cost per	1	SY \$3.17
	125,001 to 150,000 Square Yards – Cost per	1	SY \$3.17
	150,001 to 200,000 Square Yards – Cost per	1	SY \$3.17
	200,001 to 225,000 Square Yards – Cost per	1	SY \$3.17
	225,001 to 250,000 Square Yards – Cost per	1	SY \$3.17
	250,001 and Over – Cost per	1	SY \$3.17
Ic.	Traffic Control per mile		
	Arterial Streets	1	Mile \$4,000.00
	Collector Streets	1	Mile \$2,900.00
	Residential Streets	1	Mile \$1,750.00
Id.	Replacement of Road Markings in Conjunction with a Chip Seal Application Project:		
	Long Line (Yellow)	1	LF \$0.30
	Lone Line (White)	1	LF \$0.30
	Double Yellow (4" Yellow)	1	LF \$0.55
	Skip Line (4" Wide White 15' Stripe/25' Spacing)	1	LF \$0.20
	Thermo Plastic Cross Walks (12" White)	1	LF \$2.60
	Thermo Plastic Cross Walks / Stop bars (12" White)	1	LF \$2.60
	Thermo Plastic Cross Walks Yellow	1	LF \$2.60
	Thermo Plastic Cross Walks / Stop bars (12" Yellow)	1	LF \$2.60
	Center Turn Lane (4" Wide Yellow)	1	LF \$0.75
	Holding Bar (8" White)	1	LF \$0.55
	V holding Bar (8" White)	1	LF \$1.10
	Squeeze Bar (8" White)	1	LF \$0.55
	Edge Line (4" White)	1	LF \$0.30
	Bike Lane (6" White)	1	LF \$0.40
	Thermo Plastic Left Turn Arrows (8' White)	1	EA \$150.00
	Thermo Plastic Right Turn Arrows (8' White)	1	EA \$150.00
	Thermo Plastic Arrow Straight (8' White)	1	EA \$150.00
	Thermo Plastic Combination Arrows (12' 9" White, 1 each)	1	EA \$200.00
	24" Solid Yellow Circle for placement of school Zone Signs (Thermo Plastic)	1	EA \$100.00
	Thermo Plastic Ahead (8" White)	1	EA \$200.00
	Thermo Plastic Bike Symbol w/Helmet (6' White)	1	EA \$400.00
	Thermo Plastic Only (8' White)	1	EA \$200.00
	Thermo Plastic Ped (8' White)	1	EA \$200.00
	Thermo Plastic School (8' White)	1	EA \$200.00
	Thermo Plastic X-Sing (8' White)	1	EA \$200.00
	Thermo Plastic Bike Symbols (8" White)	1	EA \$400.00
	Thermo Plastic "Only" Symbols (White)	1	EA \$200.00
	Remove and Replace Hydrant Markers	1	EA \$12.00

