

REPORT TO THE CITY OF PEORIA COMMUNITY SERVICES DEPARTMENT

Section 17: Centennial Plaza

November 11, 2013

Legend of Abbreviations

aff...	Above the finished ground
AR...	Accessible Route
CIL...	Change in Level
CFS...	Clear Floor Space
EPC...	Elevated Play Component
GLPC...	Ground Level Play Component

The RAC staff visited Centennial Plaza to conduct an access audit. The findings are below.

1.1 Parking – not applicable

1.2 Exterior Accessible Route - [CHECKLIST] lacks detectable warning where walkway meets vehicular way (checklist); lacks 80” due to tree limbs [CP1](#), [CP2](#), [CP12](#)

Ramps [CHECKLIST] ramp slope 9.2% [CP41](#), [CP42](#); lacks continuous handrails [CP43](#), [CP44](#), [CP45](#), [CP46](#); handrail lack extensions on one side [CP40](#), [CP47](#)

Recommendations (Centennial Plaza is a site designated with accessible features so 1.2.1 through 1.2.4 is integral to compliance with title II program access test):

- 1.2.1 ***Install compliant detectable warning*** at transitions from walkways to vehicular ways as a smart practice (checklist)
- 1.2.2 ***Maintain*** overhead clearance of min 80” (CP1, CP2, CP12)
- 1.2.3 ***Correct slope*** of ramp to max 8.33% (CP41, CP42)
- 1.2.4 ***Install handrails*** on both sides of the ramp that are continuous and have extensions on the top and bottom (CP43, CP44, CP45, CP46, CP40, CP47)

Responsible Employee	Progress Towards Completion	Recommended Phase
Brenda Rehnke Recreation Manager 623-773-7131	(insert periodic notes regarding steps taken or work completed)	PHASE ONE

1.3 Playground Designated Entry – not applicable

1.4 Playground Surface/Accessible Route within – not applicable

1.5 Transfer System – not applicable

1.6 Ramps – not applicable

1.7 Elevated Play Components – not applicable

1.8 Ground Level Play Components – not applicable

1.9 Sand box/Play tables – not applicable

1.10 Park Site - [CHECKLIST]

Mutt Mitt: lacks AR, out of reach range [CP8](#)

Amphitheatre: gaps at drains [CP33](#), [CP34](#); running slopes - 7.3% [CP24](#), [CP25](#), 6.5% [CP27](#), [CP28](#), 6.4% [CP29](#), [CP30](#); cross slope – 3.4% [CP31](#), [CP32](#)

Recommendations (Centennial Plaza is a site designated with accessible features so 1.10.1 through 1.10.4 is integral to compliance with title II program access test):

- 1.10.1 **Relocate** mutt mitt to be in reach range of the AR and **lower** to max 48" agl to the highest operable part (CP8)
- 1.10.2 **Replace** drains in amphitheater with ones having gaps max .5" (CP33, CP34)
- 1.10.3 **Correct or repair** running slope along AR within amphitheater to max 5% (CP24, CP25, CP27, CP28, CP29, CP30)
- 1.10.4 **Correct or repair** cross slope along AR within amphitheater to max 2.08% (CP31, CP32)

Responsible Employee	Progress Towards Completion	Recommended Phase
Brenda Rehnke Recreation Manager 623-773-7131	(insert periodic notes regarding steps taken or work completed)	PHASE TWO

1.11 Shelters/Picnic Areas - [CHECKLIST] all lack AR to entry (checklist); CIL at entries [CP36](#), [CP37](#), [CP39](#)

Recommendations (in the alternative, leave as is and designate other Department shelters as accessible):

- 1.11.1 **Provide** ramps to shelters for access (CP36, CP37, CP39, checklist)

Responsible Employee	Progress Towards Completion	Recommended Phase
Brenda Rehnke Recreation Manager 623-773-7131	(insert periodic notes regarding steps taken or work completed)	PHASE THREE

1.12 Park Buildings – not applicable

1.13 Other – Assembly area [CHECKLIST] seating lacks designation signage [CP3](#), [CP4](#), [CP5](#), [CP6](#), [CP7](#); unknown seating capacity (checklist)

Recommendations (Centennial Plaza is a site designated with accessible features so 1.13.1 is integral to compliance with title II program access test):

- 1.13.1 **Acquire and mount** signage, including access symbol, designating specified number of wheelchair seats based on chart and estimated seating capacity (CP3, CP4, CP5, CP6, CP7, checklist)

Responsible Employee	Progress Towards Completion	Recommended Phase
Brenda Rehnke Recreation Manager 623-773-7131	(insert periodic notes regarding steps taken or work completed)	PHASE THREE